



50051 Mfundu Mngadi Drive, Kwamakhutha, 4126
Tel. (031) 9051390 Fax: 031 905 1399 Email: cao.CKZCAO@KZNTVET.EDU.ZA



(TO BE SUBMITTED WITH LATEST CSD REPORT)

AT:	SALES
FASCIMILE NUMBER:	0867625744
CONTACT NUMBER:	(031)9051390

DATE ADVERTISED:	23/01/2026
ENQUIRIES MAY BE DIRECTED TO:	
PHYSICAL ADDRESS:	50051 MFUNDI MNGADI DRIVE,KWAMAKHUTHA

DESCRIPTION.....FACILITIES AND INFRASTRUCTURE.....

THE FOLLOWING PARTICULARS MUST BE FURNISHED (FAILURE TO DO SO WILL RESULT IN YOUR OFFER BEING DISQUALIFIED)

[illegible][illegible]



DECLARATION OF INTEREST

Any legal person, including persons employed by the "college", or persons having a kinship with persons employed by the college, including a blood relationship, may make an offer or offers in terms of this invitation to quote (includes a price quotation, advertised competitive quote, limited quote or proposal). In view of possible allegations of favoritism, should the resulting quote, or part thereof, be awarded to persons employed by the college, or to persons connected with or related to them, it is required that the bidder or his/her authorised representative declare his/her position in relation to the evaluating/adjudicating authority where- - the bidder is employed by the state; and/or - the legal person on whose behalf the bidding document is signed, has a relationship with persons/a person who are/is involved in the evaluation and or adjudication of the quote(s), or where it is known that such a relationship exists between the person or persons for or on whose behalf the declarant acts and persons who are involved with the evaluation and or adjudication of the quote.

2. In order to give effect to the above, the following questionnaire must be completed and submitted with the quote.

2.1. Full Name of bidder/representative.....

2.2. Identity Number:

2.3. Position occupied in the Company (director, trustee, shareholder²):

2.4. Company Registration Number:

2.5. Tax Reference Number:

2.6. VAT Registration Number:

2.7. The names of all directors / trustees / shareholders / members, their individual identity numbers, tax reference numbers and, if applicable, employee / persal numbers must be indicated in paragraph 3 below.

[TICK APPLICABLE]

2.8. Are you or any person connected with the bidder presently employed by the state?

yes	no
-----	----

2.8.1. If so, furnish the following particulars: Name of person / director / trustee / shareholder/ member:

..... Name of state entity at which you or the person connected to the bidder is employed:..... Position occupied in the state institution:

2.8.2. If you are presently employed by the state, did you obtain the appropriate authority to undertake remunerative work outside employment in the public sector?

[TICK APPLICABLE]

yes	no
-----	----

2.8.2.1. If yes, did you attach proof of such authority to the quote document?

yes	no
-----	----

(Note: Failure to submit proof of such authority where applicable, may result in The disqualification of your quote

2.8.2.2. If no, furnish reasons for non-submission of such proof:

2.9. Did you or your spouse, or any of the company's directors / trustees / shareholders / members or their spouses conduct business with the college in the previous twelve months?

[TICK APPLICABLE]

yes	no
-----	----



higher education & training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA

CENTRAL OFFICE

50051 Mfundu Mngadi Drive, Kwamakhutha, 4126
Tel. (031) 9057081 Fax: 0867625744 Email: SuamadoA.CKZCAO@KZNTVET.EDU.ZA



2.9.1. If so, furnish particulars:.....

2.10. Do you, or any person connected with the bidder, have any relationship (family, friend, other) with a person employed by the college and who may be involved with the evaluation and or adjudication of this quote?
[TICK APPLICABLE]

yes		no	
-----	--	----	--

2.10.1. If so, furnish particulars:.....

2.11. Are you, or any person connected with the bidder, aware of any relationship (family, friend, other) between any other bidder and any person employed by the college who may be involved with the evaluation and or adjudication of this quote?

[TICK APPLICABLE]

yes		no	
-----	--	----	--

2.11.1. If so, furnish particulars:.....

2.12. Do you or any of the directors / trustees / shareholders / members of the company have any interest in any other related companies whether or not they are bidding for this contract?
[TICK APPLICABLE]

yes		no	
-----	--	----	--

2.12.1. If so, furnish particulars:.....

3. Full details of directors / trustees / members / shareholders. NB: Coastal College will validate details of directors / trustees / members / shareholders on CSD. It is the suppliers' responsibility to ensure that their details are up-to-date and verified on CSD. If the Department cannot validate the information on CSD, the quote will not be considered and passed over as non-compliant according to National Treasury Instruction Note 4 (a) 2016/17.

4 DECLARATION

I, THE UNDERSIGNED (NAME).....CERTIFY THAT THE INFORMATION FURNISHED IN PARAGRAPHS 2.

I ACCEPT THAT THE COLLEGE MAY REJECT THE QUOTE OR ACT AGAINST ME SHOULD THIS DECLARATION PROVE TO BE FALSE.

.....			
Name of Bidder	Signature	Position	Date

02415



higher education
& training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA



Your Pioneering Centre of Excellence

COASTAL KZN TVET COLLEGE

50051 MFUNDI MNGADI DRIVE, KWAMAKHUTHA, 4126

TEL: (031) 905 7000 FAX: (031) 905 1399 E-mail: cao.CKZCAO@KZNTVET.EDU.ZA

GL NO

REQUISTION

FOR PURCHASE OF GOODS / SERVICES

Name of person requesting goods/services: Sithole SB

Division: Facilities + Infrastructure

[illegible]

SIGNATURE OF COMPLIER: [Signature] DESIGNATION: Facilities DATE: _____

MOTIVATION/COMMENTS:

SIGNATURE OF SUPERVISOR: [Signature] DESIGNATION: Manager DATE: 10/01/26

DEMAND SECTION:

CONFIRMATION THAT THE SPECIFICATIONS ARE CORRECT

SIGNATURE OF OFFICIAL:  DESIGNATION: A.D. Seta DATE: 15/01/20

Detailed Scope of Work (SoW)

C. Hospitality Workshop

- **Paint office ceiling: 16 m²** (prepare, prime as needed, 2 coats acrylic).
- **Paint office walls: 35 m²** (prepare, spot repair, 2 coats washable acrylic).
- **Floor tiling office: 16 m²:**
 - Lift existing (if any), level screed.
 - Supply & lay porcelain/ceramic tiles ($\geq 600 \times 600$ or to match existing), grouting, trims, skirting tile (where required).
- **Provisional Sum: R 5,000** for replacement of other damaged floor/wall tiles and light tubes (materials & labour).

D. ECDP (TTA Building)

Electrical & Lighting

- Replace **6x light tubes** like-for-like (verify lamp type and control gear).

Roofing

- Inspect and **repair roof leaks**.
- **Apply asbestos sealant** (if asbestos-containing material present) following **licensed method & legal compliance**.
- **Repaint roof** to match existing on **30 m²** area (high-adhesion roof coating).
- **Clean roof slab; repair any waterproofing damage (30 m²).**

Windows & Doors

- Service/restore **window operability** (stays, hinges, handles).
- Remove **3 old air conditioners** and **close openings** with **glazed panes** in suitable aluminium frames to match.
- **Paint all window frames** (prep & rust treatment where steel).
- **Wall painting: 40 m².**
- **Door frame** paint.
- **Concrete beam paint: 40 m²** (contrasting colour).
- **Entrance door:** wood reconditioning (sand, repair, seal/varnish), replace **1x toughened glass pane** and **door lock**.
- **Office door:** varnishing and **lock replacement**.

Partitions

- Install **drywall:**
 - **2.0 m (L) × 2.2 m (H).**
 - **2.5 m (L) × 2.2 m (H).**
 - **Over-door top drywall: 2.0 m (L)** (height to match transom requirement).
- Partition one corner:
 - **2.35 m (L) × 2.2 m (H)** drywall.

- **6.15 m (L) L-shape aluminium & toughened glass wall with 1x standard hinged door.**
- Shelving: Remove & replace **14 m × 0.33 m brown hardwood shelves** (allow for brackets/cleats).

E. TTA & TTB Blocks

- Replace **suspended ceiling: 168 m²** (tiles + grid; include brandlering/hangers as required).
- Replace **missing window glass** (quantity TBC – provisional).
- Replace **all burnt light tubes** (quantity TBC – provisional).
- **Wall painting: 100 m²** (prep, 2 coats).
- Replace **18x damaged/missing flip-up/lecture chairs** (equal or better spec; fixings included).
- Replace **entrance aluminium door lock** (mortice/Euro profile to match system).
- Replace **door self-closing mechanism** (adjust door alignment).
- Repair **3x wall plugs/sockets** (faceplates, refix, test).

F. Restaurant

Shopfront

- Remove existing aluminium folding door.
- Supply & install new **full shopfront: H = 3.036 m × L = 9.26 m:**
 - Powder-coated aluminium system with **toughened safety glass**.
 - Include **1–2 door leaves** (swing/sliding) with standard hardware, seals, and thresholds.
 - Make good reveals, sills, waterproofing, and finishes.

New Internal Office (Modular)

- Build **2.0 m (W) × 3.0 m (L) × 3.036 m (H)** with **50 mm insulated modular panels**.
- **1x standard door** (solid or glazed panel door).
- **1x 12,000 BTU split-type air conditioner** (install & commission).

Window

- Install **aluminium window** sized to fit **3.39 m (L) × 2.2 m (H)** opening (final module to manufacturer system).
- Position to align with **existing external burglar bars** (maintain security; adjust bars if needed).

2) Assumptions & Clarifications

- All quantities are **SSSC**. Drawings and final layouts (walkways, demarcation, glass modules) to be agreed upon before execution.
- The **asbestos-related scope** will be undertaken by **licensed personnel** with statutory notifications, PPE, and disposal compliance.
- **Electrical** repairs include re-termination and testing, but exclude DB replacements unless specified.
- **Glazing is toughened safety glass** where noted; thickness as per span/standard (typically 6–10 mm for internal, 10–12 mm for shopfront).

- **Painting** includes surface preparation, patching minor defects, and two finish coats unless otherwise stated.
- Waste removal and site protection are included in all items.
- Provisional/unspecified quantities (e.g., missing window pane count, total tubes) are included as **Provisional Sums (PS)** or **Rate-Only lines** for transparency.

SWINTON CAMPUS (QTCOM PROGRAMME PREPARATION)

BOQ (For Service Provider Completion)

Columns: Fill in *Rate* and *Amount*; adjust *Qty* if site measurements differ.

Key Units: m² (square meter), m (linear meter), No. (number), PS (Provisional Sum), LS (Lump Sum)

C. Hospitality Workshop						
C1	Paint ceiling (office)	m ²	16			2 coats of acrylic
C2	Paint walls (office)	m ²	35			Washable acrylic
C3	Floor tiling (incl. skirtings & trims)	m ²	16			Ceramic 600mmx600mm;
C4	Replace damaged tiles & light tubes (Provisional Sum)	PS	1	5,000.00	5,000.00	Materials & labour
D. ECDP (TTA Building)						
D1	Replace light tubes (like-for-like)	No.	6			Confirm type & control gear
D2	Roof leak repairs – localized	PS	1			Includes patching and sealing.
D3	Asbestos encapsulation/seal (licensed)	m ²	471			Compliance incl.
D4	Roof repaint to match	m ²	471			High-adhesion roof coating
D5	Clean the roof slab & repair the waterproofing	m ²	30			Membrane/bitumen as needed
D6	Service/restore window functionality	LS	1			Stays/hinges/handles
D7	Remove 3x old ACs & infill with glazed panes	No.	3			Aluminium framing to match
D8	Paint window frames	m ²	PS			Measure on site (face area)
D9	Wall painting	m ²	40			2 coats
D10	Door frame painting	No.	1			
D11	Concrete beam painting (contrast colour)	m ²	40			
D12	Entrance door – wood reconditioning	No.	1			Sand, repair, seal/varnish
D13	Replace the toughened glass pane (entrance door)	No.	1			Size to match existing

D14	Entrance door lock replacement	No.	1			
D15	Office door varnishing	No.	1			
D16	Office door lock replacement	No.	1			
D17	Install drywall 2.0 m × 2.2 m and painting	m ²	4.40			
D18	Install drywall 2.5 m × 2.2 m and painting	m ²	5.50			
D19	Over-door top drywall 2.0 m and painting(height TBC)	m ²	PS			Assume 0.5–0.8 m H
D20	Install drywall 2.35 m × 2.2 m and painting	m ²	5.17			
D21	L shape aluminium & glass wall (incl. 1 door)	m	6.15			Height 2.2 m
D22	Standard door in glass wall (complete)	No.	1			Hinges/locks/handles
D23	Remove & replace hardwood shelves (0.33 m deep)	m	14.00			Include brackets/cleats
D24	Clean all roof gutters	m	37			

E. TTA & TTB Blocks

E1	Suspended ceiling replacement (grid + tiles)	m ²	168			The existing steel frame(grid) can be utilised if it is still in good condition
E2	Replace missing window glass	No.	PS			Site count required
E3	Replace burnt light tubes	No.	PS			Site count/type required
E4	Paint internal walls	m ²	100			2 coats
E5	Replace the lecture flipping chairs	No.	18			Supply & fix
E6	Replace the entrance aluminium door lock	No.	1			

E7	Replace the door self-closing mechanism	No.	1			Adjust & set
E8	Repair wall plugs/sockets	No.	3			Test & certify
F. Restaurant						
F1	Remove the existing aluminium folding door	LS	1			Careful removal and keep safe.
F2	New aluminium & toughened glass shopfront	m ²	28.09			3.036 m × 9.26 m
F3	Shopfront doors (incl. hardware)	No.	PS			1–2 leaves; confirm operation
F4	Make good reveals/sills & waterproofing	LS	1			Plaster, seal, paint as needed
F5	Modular office (50 mm insulated panels)	m ² (wall)	15.18			Perimeter: 2+3=5 m(L) × 3.036 m H
F6	Modular office – standard door	No.	1			
F7	AC 12,000 BTU – supply, install & commission	No.	1			
F8	Aluminium window to 3.39 m × 2.2 m opening	m ²	7.46			Position outside burglar bars
F9	Adjust/retain external burglar bars	LS	1			Modify to suit the window install
	Sum					